

BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/08/2020-21 Dated: 26-11-2020



APPROVED TENDER SCHEDULE - 'B'

Item 08

Name of Work :-Improvements to roads and drains Dobhighat and Surrounding areas at Ananthapura in ward no:03 Attur

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri Umesh N	
				Rate	Rate in Words
1	KSRB 300-3 : Earthwork Excavation by manual means for roads, drains and similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per Specifications with all lead and lift as per direction of Engineer in charge.	Cum	1330.75	207.60	Two Hundred Seven Paise Sixty Only
2	KSRB M2100-10: Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @ 0.89 cum and fine aggregates @ 0.46 cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centring complete as per specifications with all lead and lift as per direction of Engineer in charge.	Cum	243.29	5509.33	Five Thousand Five Hundred Nine Paise ThirtyThree Only
3	Providing and laying in position plain cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.43 cum machine mixed, well compacted for walls and bottom including centring shuttering cost of material HOM of machinery curing etc., complete excluding cost of steel as per Morth Specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per Specifications with all lead and lift as per direction of Engineer in charge.	Cum	394.74	7189.42	Seven Thousand One Hundred EightyNine Paise FourtyTwo Only

	KSRRB M2300-14: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour HOM of machinery complete as per specifications with all lead and lift as per direction of Engineer in charge.	Tonne	25.86	66712.16	SixtySix Thousand Seven Hundred Twelve Paise Sixteen Only
5	Providing and Fixing RCC pre cast cover Slab 100mm thick for drain made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work, lift charges, curing and concrete finished on both sides etc., Complete As per drawing and direction of Engineer IN charge.	Sqm	1008.45	2337.00	Two Thousand Three Hundred ThirtySeven Only
6	Providing and Fixing RCC pre cast cover Slab 250 mm thick for Culverts made of Plain/Reinforced Cement Concrete Design mix M25 with OPC @ 340 Kgs, with 20 mm and down size graded granite metal coarse aggregates @ 0.70 cum and Fine aggregates @ 0.47 cum with superplasticizer @ 3 ltrs confirming to 189103-1999 Reaffirmed-2008, Open Foundation complete as per Drawing and Technical specification including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications and pointing for joints 1:3 cement mortar including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per and as per the directions of Engineer in charge.	Sqm	18.00	5418.00	Five Thousand Four Hundred Eighteen Only
7	KSRRB-300: Compaction KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications.	Sqm	416.00	6.00	Six Only

Cement concrete pavement. Constructing unreinforced, plain cement concrete for pavements, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design M30 with 25 mm and down size graded granite metal coarse aggregates and fine aggregates with superplasticiser @ 3 lts confirming to IS9103-1999 Reaffirmed-2008 mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing) & Spreading the concrete with shovels, rakers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane of impermeable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing with all lead and lift as per the direction of Engineer In charge.


Cum

62.40

5354.02

Five Thousand
Three Hundred
FiftyFour Paise
Two Only

Signature of the Contractor



Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

